

BELL/SIREN TEST

To test the sirens to your security system:

Enter your PIN CODE Press * key, enter the digit "6", then the digit "3", then push the # key.

The siren and keypads will sound for 3 seconds. .

If the test message was successfully transmitted to the central station, the keypad will beep twice.

Control Room Monitoring TEST

This function tests the proper monitoring test signals from your alarm system by sending a test message to the 24 hour back to base control room.

Weekends are the best time for the Control Room Testing.

To test your security system, call your central monitoring station and notify to put on test for about one hour.

Enter your PIN (if required), press the * key, enter the digit "6", then the digit "1", then push the # . If the test message was not successfully tested to the central station, the keypad will beep five times, and the SERVICE light will flash fast. Call your Control Room for assistance if this is the case.

A good test indicates there is no service light ON.

Testing your CK SYSTEMS alarm with alarmmaintenance.com.au